



Digital Commissioning & Industry Evolution

Smarter Cx Workflows for Future-Ready Buildings

Andy Heitman, CxA, EMP, CEM - Building Energy Sciences / B.E.S. Plus Tech


Andrew Rodgers - ACE IoT Solutions

April 23rd, 2026 at CxEnergy

What is Digital Commissioning?

The Digital Commissioning Process

Digital Cx applies across every phase:



What is Digital Commissioning?

- Use of digital commissioning tools across all phases and purposeful intent in the commissioning process to integrate and leverage
- Specific attention to defining requirements in Pre-Design
- Real-time validation of **BAS networks and digital systems**
- Bridges HVAC commissioning with IT/networking
- Fusion of traditional functional testing with data-driven testing
- Confirms **digital infrastructure** is built as scoped
- **Vendor-neutral:** process applies across protocols and platforms

DCx vs. Traditional Cx

- Manual testing process
- Paper-based checklists
- 'Batch' backward looking
- One-time verification
- HVAC-focused scope

Traditional Cx



- Automated validation tools
- Cloud-based Cx processes
- Real-time data analysis
- Ongoing monitoring (MBCx)
- Cross-disciplinary scope

Digital Cx



Phase 1: Pre-Design / Design

Specifying Digital Cx Requirements

- Digital Cx starts in the Design Phase
- Insufficient details in the OPR / contract requirements results in difficult to enforce in Cx
- Is specifying systems to be BACnet alone enough?
 - What to specify? How to specify?
 - “Provide BACnet compatible BAS”
- Drawing / Specifications detail level
 - What should be on drawings? What should be in specifications?



ANSI/ASHRAE Standard 135-2024
(Supersedes ANSI/ASHRAE Standard 135-2020)



A Data Communication Protocol for Building Automation and Control Networks

See the History of Revisions at the end of the standard for approval dates by the ASHRAE Standards Committee, the ASHRAE Board of Directors, and the American National Standards Institute.

This Standard is under continuous maintenance by a Standing Standard Project Committee (SSPC) for which the Standards Committee has established a documented program for regular publication of addenda or revisions, including procedures for timely, documented, consensus action on requests for change to any part of the Standard. Instructions for how to submit a change can be found on the ASHRAE® website (www.ashrae.org/continuous-maintenance).

The latest edition of an ASHRAE Standard may be purchased from the ASHRAE website (www.ashrae.org) or from ASHRAE Customer Service, 180 Technology Parkway, Peachtree Corners, GA 30092. E-mail: orders@ashrae.org. Fax: 678-519-2129. Telephone: 404-636-8400 (worldwide), or toll free 1-800-527-4723 (for orders in US and Canada). For reprint permission, go to www.ashrae.org/permissions.

© 2024 ASHRAE ISSN 1041-2336



BACnet/IP vs. BACnet MSTP

BACnet/IP

Standard Ethernet networks

Higher bandwidth and speed

Supports IT security practices

Enables remote access

Special attention to Subnetting for BACnet

BACnet MSTP

Serial RS-485 Protocol

Lower cost, simpler networks

Limited bandwidth

Requires IP router to bridge

- Protocol choice drives physical network design and installation

BACnet Secure Connect (BACnet/SC)

- TLS-encrypted BACnet over WebSockets
- Requires PKI: certificate provisioning and lifecycle management
- Hub-and-spoke topology replaces broadcast model
- Certificate management becomes a formal Cx and O&M requirement

And more...

- BACnet IP (T1L & T1S)

Interpreting OPRs: “Native BACnet”

- “Native BACnet” ≠ interoperable out of the box
- Which protocol? IP, MSTP, SC — each has different Cx needs
- Proprietary extensions can hide behind “native” claims
- What should Cx verify: data export capability, API access, multi-vendor interoperability
- Owner needs for usage of building data after occupancy?
- Does project / owner require a Division 25 contractor (S.I.)

Network Infrastructure Planning

- BMS contractor vs. structured cabling contractor installation responsibilities
- Managed vs. unmanaged switches: most enterprise owners require managed
- VLANs increasingly common for BMS network segmentation
- IT-managed vs. BMS contractor-managed infrastructure: define ownership early
- Plan remote access method for BMS systems during design
- Network riser diagram on controls design drawings


BMS Device and Point Naming

- Consistent / structured point naming conventions
(SAT, Supply_Temp, SA_Tmp, Temp_Supply, SATemp, SupplyAirTemp,...)
- Naming for clarity and usability
- Making systems readable and maintainable
- Naming that supports troubleshooting
- Data consistency across systems
- Future-proofing the Owners BMS for new applications / upgrades
- Control point metadata requirements (naming, tagging, semantic model)

BMS Device and Point Naming

- Standardized device naming (using BACnet device object name value)

- Should not need a secret-decoder ring to determine what BACnet Device is what actual system / equipment!



The screenshot shows a software interface with a navigation menu at the top: PROPERTIES, TEAM, SYSTEMS, PROVIDERS, METERS, METRICS, UTILITIES, and DIAGNOSTICS. Below this is a sub-menu: SETUP, EMAILS, FTP, ACE IOT, and ACE IOT DEVICES. A search bar labeled 'Search Devices' is present. The main content is a table with the following columns: Device Address, Device Id, Device Name, Points, and Collect Enabled Points. The 'Device Name' column is highlighted with a red border. The table contains 20 rows of data, including various ABB ECLIPSE devices and other equipment like Betelgeuse and Dev_MSTP.

Device Address	Device Id	Device Name	Points	Collect Enabled Points
2450:1	24501	ABB ECLIPSE 80 ACH580 24501	119	0
2450:2	24502	ABB ECLIPSE 80 ACH580 24502	119	0
2450:3	24503	ABB ECLIPSE 80 ACH580 24503	119	0
2450:4	24504	ABB ECLIPSE 80 ACH580 24504	119	0
2450:5	24505	ABB ECLIPSE 80 ACH580 24505	119	0
2450:7	24507	ABB ECLIPSE 80 ACH580 24507	119	0
2450:8	24508	ABB ECLIPSE 80 ACH580 24508	119	0
2451:1	24511	ABB ECLIPSE 80 ACH580 24511	119	0
2451:2	24512	ABB ECLIPSE 80 ACH580 24512	119	0
2451:3	24513	ABB ECLIPSE 80 ACH580 24513	119	0
2450:15	24522	ABB ECLIPSE 80 ACH580 24522	119	0
2451:23	24523	ABB ECLIPSE 80 ACH580 24523	119	0
192.168.50.111	708113	Betelgeuse	1	0
2450:6	2450	Dev_MSTP	148	0
192.168.50.3	240060	device240060	905	0
2401:1	240101	device240101	27	0
2401:2	240102	device240102	27	0
2401:3	240103	device240103	210	26
2401:4	240104	device240104	27	0
2401:5	240105	device240105	27	0
2401:6	240106	device240106	27	0

Integration Scope & Control Point Decisions

Should we "integrate" EVERYTHING available?

- Chillers, Boilers, VFDs, AMFS, Switchgear, Lighting, etc...
- Points, points, and more points!!!

Control point decisions – controlling with communicated points?

- Using BACNET points vs 'hard-wired' points for control
- Using hard-wired points increases control reliability

Quick Trivia Facts:

How many points are available from some common BAS manufacturers for VAV Air Terminal Units:

Trane – 133 points

Siemens – 325 points

(squeeze-off reheat type)

Integration Scope & Control Point Decisions

ACE Myrtle Grove 131 of 15932 Points

DEVICE NAME: AC DRIVE 46401 x

Search Points Page 1 of 3 Process Start Date... Process End Date...

<input type="checkbox"/>	Name ^	System	Collect	Int.	Device Name	Device ID	Device Address	Object Type	Inst #	Units	Latest Value	Latest Time	Metric Name
<input type="checkbox"/>	AC Drive 46401	AHU-1.2	<input type="checkbox"/>	0	AC Drive 46401	46401	46401:1	device	46401				
<input type="checkbox"/>	Accel-1-Seconds	AHU-1.2	<input type="checkbox"/>	0	AC Drive 46401	46401	46401:1	analogValue	23	secondr			
<input type="checkbox"/>	Active-Fault	AHU-1.2	<input checked="" type="checkbox"/>	15	AC Drive 46401	46401	46401:1	analogValue	18	no-units			
<input type="checkbox"/>	Active-Fault-1	AHU-1.2	<input type="checkbox"/>	15	AC Drive 46401	46401	46401:1	multiStateValue	1				
<input type="checkbox"/>	Active-Fault-2	AHU-1.2	<input type="checkbox"/>	15	AC Drive 46401	46401	46401:1	multiStateValue	2				
<input type="checkbox"/>	Active-Fault-3	AHU-1.2	<input type="checkbox"/>	15	AC Drive 46401	46401	46401:1	multiStateValue	3				
<input type="checkbox"/>	Active-Warning-1	AHU-1.2	<input type="checkbox"/>	0	AC Drive 46401	46401	46401:1	multiStateValue	4				
<input type="checkbox"/>	Active-Warning-2	AHU-1.2	<input type="checkbox"/>	0	AC Drive 46401	46401	46401:1	multiStateValue	5				
<input type="checkbox"/>	Active-Warning-3	AHU-1.2	<input type="checkbox"/>	0	AC Drive 46401	46401	46401:1	multiStateValue	6				
<input type="checkbox"/>	AI1-Monitor	AHU-1.2	<input type="checkbox"/>	0	AC Drive 46401	46401	46401:1	analogInput	0	percent			
<input type="checkbox"/>	AI2-Monitor	AHU-1.2	<input type="checkbox"/>	0	AC Drive 46401	46401	46401:1	analogInput	1	percent			
<input type="checkbox"/>	AO1-Command	AHU-1.2	<input type="checkbox"/>	0	AC Drive 46401	46401	46401:1	analogOutput	0	percent			
<input type="checkbox"/>	AO1-Monitor	AHU-1.2	<input type="checkbox"/>	0	AC Drive 46401	46401	46401:1	analogValue	21	percent			
<input type="checkbox"/>	AO2-Command	AHU-1.2	<input type="checkbox"/>	0	AC Drive 46401	46401	46401:1	analogOutput	1	percent			
<input type="checkbox"/>	AO2-Monitor	AHU-1.2	<input type="checkbox"/>	0	AC Drive 46401	46401	46401:1	analogValue	22	percent			
<input type="checkbox"/>	At-Setpoint-Monitor	AHU-1.2	<input type="checkbox"/>	0	AC Drive 46401	46401	46401:1	binaryValue	8				
<input type="checkbox"/>	Control-Override-Command	AHU-1.2	<input type="checkbox"/>	0	AC Drive 46401	46401	46401:1	binaryValue	18				
<input type="checkbox"/>	Control-Override-Monitor	AHU-1.2	<input type="checkbox"/>	0	AC Drive 46401	46401	46401:1	binaryValue	19				
<input type="checkbox"/>	Data-IO-1	AHU-1.2	<input type="checkbox"/>	0	AC Drive 46401	46401	46401:1	analogValue	120	no-units			
<input type="checkbox"/>	Data-IO-10	AHU-1.2	<input type="checkbox"/>	0	AC Drive 46401	46401	46401:1	analogValue	129	no-units			
<input type="checkbox"/>	Data-IO-2	AHU-1.2	<input type="checkbox"/>	0	AC Drive 46401	46401	46401:1	analogValue	121	no-units			
<input type="checkbox"/>	Data-IO-3	AHU-1.2	<input type="checkbox"/>	0	AC Drive 46401	46401	46401:1	analogValue	122	no-units			
<input type="checkbox"/>	Data-IO-4	AHU-1.2	<input type="checkbox"/>	0	AC Drive 46401	46401	46401:1	analogValue	123	no-units			
<input type="checkbox"/>	Data-IO-5	AHU-1.2	<input type="checkbox"/>	0	AC Drive 46401	46401	46401:1	analogValue	124	no-units			

AHU Fan ABB VFD Example – 131 points available!

We selected 'just' 14 points to collect data for

ACE Myrtle Grove 14 of 15932 Points

COLLECT: ENABLED x DEVICE NAME: AC DRIVE 46401 x

Search Points Page 1 of 1 Process Start Date... Process End Date...

<input type="checkbox"/>	Name ^	System	Collect	Int.	Device Name	Device ID	Device Address	Object Type	Inst #	Units	Latest Value	Latest Time	Metric Name
<input type="checkbox"/>	Active-Fault	AHU-1.2	<input checked="" type="checkbox"/>	15	AC Drive 46401	46401	46401:1	analogValue	18	no-units	0	4/12/26 11:00 AM	
<input type="checkbox"/>	HAND-AUTO-Monitor	AHU-1.2	<input checked="" type="checkbox"/>	15	AC Drive 46401	46401	46401:1	binaryValue	4		0	4/12/26 11:00 AM	
<input type="checkbox"/>	HAND-AUTO-Reference	AHU-1.2	<input checked="" type="checkbox"/>	15	AC Drive 46401	46401	46401:1	multiStateValue	0		3	4/12/26 11:00 AM	
<input type="checkbox"/>	Input-Reference-1	AHU-1.2	<input checked="" type="checkbox"/>	15	AC Drive 46401	46401	46401:1	analogValue	16	percent	0	4/12/26 11:00 AM	
<input type="checkbox"/>	Motor-Temp-Degrees-C	AHU-1.2	<input checked="" type="checkbox"/>	15	AC Drive 46401	46401	46401:1	analogValue	15	degrees-celsius	20	4/12/26 11:00 AM	
<input type="checkbox"/>	OK-FAULT-Monitor	AHU-1.2	<input checked="" type="checkbox"/>	15	AC Drive 46401	46401	46401:1	binaryValue	2		0	4/12/26 11:00 AM	
<input type="checkbox"/>	Output-Current	AHU-1.2	<input checked="" type="checkbox"/>	15	AC Drive 46401	46401	46401:1	analogValue	4	amperes	0	4/12/26 11:00 AM	
<input type="checkbox"/>	Output-Current-Range	AHU-1.2	<input checked="" type="checkbox"/>	15	AC Drive 46401	46401	46401:1	analogValue	32	percent	0	4/12/26 11:00 AM	
<input type="checkbox"/>	Output-Freq	AHU-1.2	<input checked="" type="checkbox"/>	15	AC Drive 46401	46401	46401:1	analogValue	1	hertz	0	4/12/26 11:00 AM	
<input type="checkbox"/>	Output-Power	AHU-1.2	<input checked="" type="checkbox"/>	15	AC Drive 46401	46401	46401:1	analogValue	6	kilowatts	0	4/12/26 11:00 AM	
<input type="checkbox"/>	Output-Speed	AHU-1.2	<input checked="" type="checkbox"/>	15	AC Drive 46401	46401	46401:1	analogValue	31	percent	0	4/12/26 11:00 AM	
<input type="checkbox"/>	Output-Voltage	AHU-1.2	<input checked="" type="checkbox"/>	15	AC Drive 46401	46401	46401:1	analogValue	3	volts	0	4/12/26 11:00 AM	
<input type="checkbox"/>	RUN-STOP-Monitor	AHU-1.2	<input checked="" type="checkbox"/>	15	AC Drive 46401	46401	46401:1	binaryValue	0		0	4/12/26 11:00 AM	
<input type="checkbox"/>	Running-Hours	AHU-1.2	<input checked="" type="checkbox"/>	15	AC Drive 46401	46401	46401:1	analogValue	14	hours	6018	4/12/26 11:00 AM	

Phase 2: Construction / Acceptance

How Digital Cx Has Evolved

Digital Commissioning used to just mean...

- Using a Cx software for 'digital' checklists / tests
- On-line Deficiency tracking in lieu of paper-based (or desktop software) for improved


Digital Commissioning enabled by design choices is now...

- Assessing system readiness via earlier access to BMS data
- Trend data access during Cx Team Meetings
- Reduce time to assess trend data by cloud-based software tools
- Enhances functional testing by using real-time BACnet data to validate performance faster, more consistently, and with *less* manual effort.


Data-Driven Functional Testing

Functional Testing evolving from Manual testing to Data Driven means:


- Live BACnet data feeds directly into Cx software
- Logic / scripts evaluate system behavior
- Tools can flag failures or anomalies automatically
- Sample-based testing eliminated or reduced
- Construction progress independently verified
- AFDD possible PRIOR to Functional Testing
- Automatically refreshing system trend charts
- Data available to the entire Commissioning Team



Data-Driven Functional Testing



Data-Driven Functional Testing



Non-Traditional Scopes in Digital Cx

- Document the network set-up and confirm health
- More easily verify device and point naming compliance

ACE Myrtle Grove

COLLECT: ENABLED ✕ NAME: DISCHARGEAIRTEMP ✕ SYSTEM: AHU ✕

Search Points Page 1 of 1 Process Start Date... Process End Date...

<input type="checkbox"/>	Name	System	Collect	Int.	Device Name ^	Device ID	Device Address
<input type="checkbox"/>	Drivers.NrioNetwork.AHU1_1_R34_1.points.DischargeAirTemp	AHU-1.1	<input checked="" type="checkbox"/>	15	MyrtleGrove_AHU1_1_46100	46100	10.46.12.10
<input type="checkbox"/>	Drivers.NrioNetwork.AHU1_2_R34_1.points.DischargeAirTemp	AHU-1.2	<input checked="" type="checkbox"/>	15	MyrtleGrove_AHU1_2_46400	46400	10.46.12.40
<input type="checkbox"/>	Drivers.NrioNetwork.AHU1_3_R34_2.points.ReHeatDischargeAirTemp	AHU-1.3	<input checked="" type="checkbox"/>	15	MyrtleGrove_AHU1_3_46700	46700	10.46.12.70
<input type="checkbox"/>	Drivers.NrioNetwork.AHU1_3_R34_1.AhuLogic.DischargeAirTemperature	AHU-1.3	<input checked="" type="checkbox"/>	15	MyrtleGrove_AHU1_3_46700	46700	10.46.12.70
<input type="checkbox"/>	Drivers.NrioNetwork.AHU1_3_R34_1.points.DischargeAirTemp	AHU-1.3	<input checked="" type="checkbox"/>	15	MyrtleGrove_AHU1_3_46700	46700	10.46.12.70
<input type="checkbox"/>	Drivers.NrioNetwork.AHU1_4_R34_1.points.DischargeAirTemp	AHU-1.4	<input checked="" type="checkbox"/>	15	MyrtleGrove_AHU1_4_46800	46800	10.46.12.80
<input type="checkbox"/>	Drivers.NrioNetwork.AHU2_5_R34_1.points.DischargeAirTemp	AHU-2.5	<input checked="" type="checkbox"/>	15	MyrtleGrove_AHU2_5_461000	461000	10.46.12.100
<input type="checkbox"/>	Drivers.NrioNetwork.AHU2_6_R34_1.points.DischargeAirTemp	AHU-2.6	<input checked="" type="checkbox"/>	15	MyrtleGrove_AHU2_6_461300	461300	10.46.12.130

ACE Myrtle Grove


COLLECT: ENABLED ✕ NAME: SPACE TEMPERATURE LOCAL ✕ DEVICE NAME: ATU ✕

Search Points Page 1 of 2

<input type="checkbox"/>	Name	System	Collect	Int.	Device Name ^	Device ID	Device Address
<input type="checkbox"/>	Space Temperature Local	ATU-1.1.01	<input checked="" type="checkbox"/>	15	ATU-1.1.01	11	10.46.12.11
<input type="checkbox"/>	Space Temperature Local	ATU-1.1.02	<input checked="" type="checkbox"/>	15	ATU-1.1.02	12	10.46.12.12
<input type="checkbox"/>	Space Temperature Local	ATU-1.1.03	<input checked="" type="checkbox"/>	15	ATU-1.1.03	13	10.46.12.13
<input type="checkbox"/>	Space Temperature Local	ATU-1.1.04	<input checked="" type="checkbox"/>	15	ATU-1.1.04	14	10.46.12.14
<input type="checkbox"/>	Space Temperature Local	ATU-1.1.05	<input checked="" type="checkbox"/>	15	ATU-1.1.05	15	10.46.12.15
<input type="checkbox"/>	Space Temperature Local	ATU-1.1.06	<input checked="" type="checkbox"/>	15	ATU-1.1.06	16	10.46.12.16
<input type="checkbox"/>	Space Temperature Local	ATU-1.1.07	<input checked="" type="checkbox"/>	15	ATU-1.1.07	17	10.46.12.17
<input type="checkbox"/>	Space Temperature Local	ATU-1.1.08	<input checked="" type="checkbox"/>	15	ATU-1.1.08	18	10.46.12.18
<input type="checkbox"/>	Space Temperature Local	ATU-1.1.09	<input checked="" type="checkbox"/>	15	ATU-1.1.09	19	10.46.12.19
<input type="checkbox"/>	Space Temperature Local	ATU-1.1.10	<input checked="" type="checkbox"/>	15	ATU-1.1.10	20	10.46.12.20
<input type="checkbox"/>	Space Temperature Local	ATU-1.1.11	<input checked="" type="checkbox"/>	15	ATU-1.1.11	21	10.46.12.21
<input type="checkbox"/>	Space Temperature Local	ATU-1.1.12	<input checked="" type="checkbox"/>	15	ATU-1.1.12	22	10.46.12.22
<input type="checkbox"/>	Space Temperature Local	ATU-1.1.13	<input checked="" type="checkbox"/>	15	ATU-1.1.13	23	10.46.12.23
<input type="checkbox"/>	Space Temperature Local	ATU-1.1.14	<input checked="" type="checkbox"/>	15	ATU-1.1.14	24	10.46.12.24
<input type="checkbox"/>	Space Temperature Local	ATU-1.1.15	<input checked="" type="checkbox"/>	15	ATU-1.1.15	25	10.46.12.25
<input type="checkbox"/>	Space Temperature Local	ATU-1.1.16	<input checked="" type="checkbox"/>	15	ATU-1.1.16	26	10.46.12.26
<input type="checkbox"/>	Space Temperature Local	ATU-1.1.17	<input checked="" type="checkbox"/>	15	ATU-1.1.17	27	10.46.12.27
<input type="checkbox"/>	Space Temperature Local	ATU-1.1.18	<input checked="" type="checkbox"/>	15	ATU-1.1.18	28	10.46.12.28
<input type="checkbox"/>	Space Temperature Local	ATU-1.1.19	<input checked="" type="checkbox"/>	15	ATU-1.1.19	29	10.46.12.29
<input type="checkbox"/>	Space Temperature Local	ATU-1.1.20	<input checked="" type="checkbox"/>	15	ATU-1.1.20	30	10.46.12.30
<input type="checkbox"/>	Space Temperature Local	ATU-1.1.21	<input checked="" type="checkbox"/>	15	ATU-1.1.21	31	10.46.12.31
<input type="checkbox"/>	Space Temperature Local	ATU-1.1.22	<input checked="" type="checkbox"/>	15	ATU-1.1.22	32	10.46.12.32
<input type="checkbox"/>	Space Temperature Local	ATU-1.2.01	<input checked="" type="checkbox"/>	15	ATU-1.2.01	41	10.46.12.41
<input type="checkbox"/>	Space Temperature Local	ATU-1.2.02	<input checked="" type="checkbox"/>	15	ATU-1.2.02	42	10.46.12.42

Network Infrastructure & Metadata Validation

- Architecture documentation
- Network topology verification
- Device addressing review
- Protocol compliance testing
- BACnet network numbers
(1 – 65,534 are valid numbers)



Network Infrastructure & Metadata Validation

- Metadata levels:
 - Level 1: Naming conventions
 - Level 2: Tagging (Haystack, Brick)
 - Level 3: Semantic models
- Automated validation scripts


Cybersecurity & Data Accessibility

Cybersecurity

- Account management and MFA
- Network encryption (TLS 1.2+)
- Segmentation and VLANs
- BACnet/SC certificate lifecycle

Cybersecurity & Data Accessibility

- Data Accessibility
- Visualization performance
- Non-proprietary formats
- API and integration support
- Trend data retention



Phase 3: Occupancy / Operations

Warranty Phase: From Reactive to Data-Driven

- Digital Commissioning extends commissioning into the Warranty period through continuous data-driven performance validation
 - Enhances / extends business opportunities beyond construction timeline
 - On-going performance monitoring enabled as a standard service
 - At end of Warranty the monitoring is extended on an annual basis
 - Long-term client relationships and dependency
- Digital commissioning turns the warranty phase from a safety net into an active performance management period.

Warranty Phase: From Reactive to Data-Driven

Traditional

- Complaint-driven
- Reactive, manual troubleshooting
- Limited access to trend data
- Delayed issue detection

Digital

- Continuous monitoring
- Automated fault detection
- Improved Contractor accountability
- Proactive, earlier issue resolution
- On-Going Optimization

Contractor Accountability and Issue Resolution

Improved Contractor Accountability


- Use data to objectively document issues
- Eliminate 'could not reproduce' scenarios
- Provide clear trend-based evidence
- Support warranty claims with data

Proactive, Earlier Issue Resolution



- Leverage historical trend data
- Understand system behavior patterns
- Reduce time to diagnose issues
- Improve response efficiency

Ongoing Optimization

- Fine-tune control sequences
- Find system outliers
- Improve energy performance
- Adjust schedules and setpoints
- Turn warranty period into optimization period




Ongoing Optimization



BACnet Data Access: The Foundational Enabler

- Direct access to system data is critical
- Enables monitoring and analytics tools
- Supports automation or hybrid execution of testing and diagnostics
- BACnet brings you the data, semantic model tells you what the data is
- Without open data access, digital Cx cannot function



Practical Digital Commissioning Adoption

Benefits of Adopting DCx

- Support owners with compliance and performance
- Technology-neutral workflows shorten project timelines
- Long-term client relationships and recurring revenue

New Business Models

New Services

- Network Audits
- Metadata Audits
- Cyber Audits

Recurring Revenue Streams

- MBCx creates ongoing service relationships
- One-year performance monitoring as a standard post-construction offering, extendable annually

The Corona Digital Cx Framework

Explore and Contribute to Corona:

github.com/ACE-IoT-Solutions/corona-digital-cx




- An open-source commissioning specification for BAS
- Licensed by CC BY-SA 4.0
- Defines the five validation areas that apply across all project phases

The Corona Digital Cx Standard



Explore and Contribute to Corona:
github.com/ACE-IoT-Solutions/corona-digital-cx

Five Validation Areas:



The Corona Digital Cx Standard



Explore and Contribute to Corona:
github.com/ACE-IoT-Solutions/corona-digital-cx

Get Involved:

- Open collaboration: issues, discussions, and pull requests welcome
- Join the Corona Digital CX Working Group
- Help shape the future of digital commissioning standards

Key Takeaways

- Digital Cx spans every project phase
- Pre-Design decisions drive Cx outcomes
- The warranty phase is a performance opportunity
- BACnet data access is foundational
- Establish company processes that support all phases
- Standardization is working

Thank You!

Andy Heitman, CxA, EMP, CEM - Building Energy Sciences / B.E.S. Plus Tech
Andrew Rodgers - ACE IoT Solutions
